

Burg school building Liestal

Services:

- General contractor
- Prefabricated timber construction
- Façade cladding
- Interior fitting

Speciality:

- Façade

We produced 36 wood modules in all with a total area of 1,452 m² for the Burg school building in Liestal. We prefabricated the modules in our plant in Eiken, then put them together on the building site. FSC-certified wood was used in the construction of the modules. The wood façade is made from native silver fir from the Basel region. The extension adds eleven classrooms, four group rooms and a common room for the students. It is designed to have a useful life that will last until it becomes necessary to renovate all the buildings on the site. Choosing a construction using sustainable wood modules meant shorter construction times and will also make it possible to use the modules for other purposes should the needs and requirements on room space change over the coming years.

Client

Buildings and Environmental Protection Department
Building Department
Rheinstrasse 29
4410 Liestal

Architect

Lorenzo Guetg
St. Alban Rheinweg 94
4052 Basel

Area:1425m²**Completion date:**

23.07.2020

Duration:

14 Mt.

Construction cost:

2.7 Mio.

Project manager:

Oliver Hasler