



Extra storey, Müllerstrasse in Zurich

Services:

- General contractor
- Prefabricated timber construction
- Interior fitting

We used our prefabricated timber construction method to create three new storeys with a gross floor space of 600 m² on Müllerstrasse in Zurich. The existing joists were reinforced and could thus be retained (wood-concrete composite floor). Solid wood was used for the intermediate floors. Häring AG was also tasked with preparing a fire safety concept and providing the entire external envelope. This comprised prefabricated façade units and roof modules with excellent heat insulation, which paved the way for a lightweight, earthquake-proof design and rapid assembly.

Client

Jugendwohnnetz
Gartenhofstrasse 15
8004 Zurich
Switzerland

Architect

Arc Architekten AG
ETH ISIA-registered architects
Binzstrasse 39
8045 Zurich
Switzerland

Area:

600 m²

Completion date:

31.12.2010

Duration:

6 months

Construction cost:

CHF 1.12 million

Project manager:

Thomas Zumsteg