



Flüestrasse Klingnau

Services:

- General contractor
- Prefabricated timber construction
- Façade cladding

The contemporary design of this detached house features impressive distinct shapes and natural materials. Its exterior walls and roof were constructed using insulated timber frame elements. The façade is made from northern Nordic spruce that has been double surface-treated. The triple-glazed, floor-level windows are mounted in powder-coated aluminium frames. The interior walls are finished with white plaster, and the ceilings are made of three-ply solid spruce panels with exposed rafters.

Client

Private

Architect

Hauenstein Märki
Steinächerweg 14
5316 Leuggern
Switzerland

Area:

327 m2

Completion date:

29.02.2016

Duration:

11 months

Construction cost:

CHF 0.38 million

Project manager:

Oliver Hasler